WEST BENGAL FOREST DEVELOPMENT CORPORATION LIMITED

(A GOVERNMENT OF WEST BENGAL UNDERTAKING)

OFFICE OF THE DIVISIONAL MANAGER

MEDINIPUR FOREST CORPORATION DIVISION

HIJLI, KHARAGPUR, PASCHIM MEDINIPUR, 721306

e-mail: mfcd@wbfdc.com

GSTIN- 19AAACW3562A5ZG

Memo No. 1754 /28-38(Q)/ 26-27 Dated-, Kharagpur 19.11.2026

QUOTATION No- 17/GPS(MFCD)/2026-27

Sealed quotation are invited from suppliers/Reputed Firms/Agencies/Govt. Contractor/Resourceful contractors and experience tax consultant for **Repairing and Maintenance of Roof Shed (North side) of Tajpur Prakriti Parjatan Kendra under Godapiasal Range of Medinipur Forest Corporation Division.** Sealed quotations are to be submitted either by post or by hand by name of **Shri Ayan Ghosh, WBFS, Divisional Manager,** Medinipur Forest Corporation Division on or before **02.12.2026 at 2.00P.M.** and same will be open in presence of Committee on **02.12.2026 at 3.00 P.M.** in the office of undersigned. Details of Terms & Conditions such work annexed herewith.

Sl. No.	Items	QTY	Maximum acceptable rates (Inclusive all taxes)	Offered rate (Inclusive all taxes)
1	**Repairing and Maintenance of Roof Shed (North side) of Tajpur Prakriti Parjatan Kendra under Godapiasal Range of Medinipur Forest Corporation Division.**	As per estimate attached	99978.00	

The quotations should reach to this office by **02.12.2026** up to 2.00 p.m. positively. The quotations will be opened tentatively on the same date at 3:30 p.m. The quotationers may remain present at the time of opening of the quotations papers.

Terms & Condition

1. The quotationers will have to produce valid GSTIN certificate, Trade Licence, and PAN card.
2. The undersigned is 6not bound to accept the lowest rate or any rate quoted may reject any part or all work without assigning any reason.
3. The undersigned reserved the right to demand from the quotationers the clarification and justification against their offer, if required.
4. The quotationers should inspect the site of works before the submission of the quotation.

5. All tools and plants, required for the works will have to be supplied by the contractor at his own cost.
6. The Contractor is liable to pay the skilled, unskilled including transport & logistics and other labour (if needed) the wages as mentioned in the PWD schedule in the district currently.
7. In case of any dispute the interpretation of the undersigned will be final.
8. The execution of the works as mentioned to the schedule will have to be started within 3 days and finished within 15 days form issue of the work order or as mentioned in work order, which will pevail, except job of parpetual nature.
9. The payment will be made after completion of all work and proper checking by the Forest Officials.
10. Work order will be issued on approval of competent authority & as per availability of fund under suitable Head of Service.
11. Payment will be made through cheque payment only.
12. Income tax and labour Cess (if applicable) will be deducted from bill.
13. **Payment will be made after receiving completion certificate from the concerned Range Manager and Bills submitted in the manner of Tax Invoice with HSN Code indicating GSTIN of this office.**

(Ayan Ghosh, WBFS)
The Divisional Manager,
Medinipur Forest Corporation Division

No. 1754 / 28-38(Q)/ 26-27 Dated:19.11.2026

Copy forwarded with a request to make a wide publicity through their "Notice Board to:

1. The Sabhadhipati, Paschim Medinipur Zilla Parishad.
2. The General Manager (H.Q.) West Bengal Forest Development Corporation Ltd.
3. The Divisional Forest Officer, Medinipur, Jhargram, Rupnarayan, Kharagpur & Purba Medinipur Forest Division.
4. The Divisional Manager, Kolkata/Bankura/Purulia Forest Corporation Division.
5. The District Information Officer, Paschim Medinipur.
6. All Range Managers, Medinipur Forest Corporation Division.
7. Asstt. Accounts Officer, Medinipur Forest Corporation Division.
8. Notice Board.
9. Online portal of departmental website www.wbfdc.com.

(Ayan Ghosh, WBFS)
The Divisional Manager,
Medinipur Forest Corporation Division

WBFDC Form No. 28

E.D Quotation

WEST BENGAL FOREST DEVELOPMENT CORPORATION LIMITED

(A Government of West Bengal Undertaking)

ESTIMATE OF WORKS

Nature Of Works:- Extension of Roof Shed (North Side) of T.P.P.K eco Resort under Godapiasal F.C Range.

Checked for Rs:-.....

.....

Head of Account:- WNEE RM

A.P.O. Item No:-.....

Sanctioned No:- 18/WNEE(RSM)1COPS/26-27.

Sanctioned Rs:- 99,978/-

Signature of the
Checking Officer

Divisional Manager
Midnapur Forest Corporation
Division

Estimate has been done as per C.P.W.D-2023

Sl no	Description of Item	No	Length	Bredth	Height	Quantity	Unit	Rate	Amount
1 (A)	**Page no- 185 , Item no- 10.16** **Steel work in built up tubular (round ,square or rectangular hollow tubes etc.) trusses etc. including cutting , hoisting , fixing in position and applying a primer coat of approved steel primer , including welding and bolted with special shaped washers etc. complete .** **10.16.1 - Hot finished welded type tubes .** For M.S. Tubular Pipe - 75 mm dia.								
	75 mm dia. Pipe	6	6			= 36	Rm		
	Wt. @ 4.73 Kg/m				36 x 4.73	= 170.28	Kg.	194.40	33,102.43
1 (B)	Calculation of one Truss Hollow regular section - ISA - 6040 - 60 x 60 size of 6.0 mm th. Weight @ 2.76 kg. / Mt. (local Rate)								
	Long side (double)	1	x 19.00 x 2.76			= 52.44	Kg		
	Short side	8	x 1.10 x 2.76			= 24.29			
						Total = 76.73	Kg		
	Hollow regular section - ISA - 6040 - 50 x 40 size of 6.0 mm th. Weight @ 2.00 kg. / Mt. (local Rate)								
	Purlin	3	x 19.00 x 1.80			= 102.60	Kg		
	Support	9	x 0.15 x 1.80			= 2.43	Kg		
						Total = 105.03	Kg		
	Total Weight = (76.73 + 105.03)					= 181.76	Kg		
						Total = 181.76	Kg.	194.40	35,333.76
2	**Page no- 201 , Item no- 12.1** **Providing corrugated G.S. Sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. Limpet washers or with G.I. Limpet washers filled with white lead , including a coat of approved steel primer and two coats of approved paint on overlaping of sheets complete (upto any pitch in horizontal / vertical or curved surfaces) excluding the cost of purlins, rafters and trussed and including cutting to size and shape wherever require .** **12.1.3 - 0.63 mm thick with Zinc coating not less than 275 gm/sqm**								
	Roof Shed	1	x 19.00 x 1.25			= 23.75	m^2		
	Total					Total = 23.75	m^2	1087.65	25,831.69
	Total Amount							Rs.	94,267.87
	Modified base estimate using correction factor on DSR 2023 on account of GST @ 0.973 =							**Rs.**	**91,722.64**
	Escalation due to Cost Index for West Midnapore Area as per G.O Memo no. 915 Dtd. 19.05.2026 Cost Index= 109, [Escalation = (109-100)% = 09%] Amount =							**Rs.**	**8,255.04**
	Total Cost including Cost Index = Rs.							**Rs.**	**99,977.68**
	Say=							**Rs.**	**99,978.00**

(Rupes Ninety nine thousand nine hundred and seventy eight only)

Submitted to the DM/MFCD for his kind Preaudit and Sanction.

Prepared & Vetted By

Range Manager
Godapiasal Range

Nirman Sahayak
Jagannathpur Gram Panchayat